


Please rate this document after reviewing at the bottom of this page.

REPLACEMENT

1. Loosen the front door checker (A) mounting bolt.

Tightening torque :

19.6 - 29.4 N·m (2.0 - 3.0 Kgf·m, 14.5 - 21.7 lb·ft)



2. Detach the clips, then remove the front door side weatherstrip (A).

Tightening torque :

19.6 - 29.4 N·m (2.0 - 3.0 Kgf·m, 14.5 - 21.7 lb·ft)



3. Install in the reverse order of removal.

Replace any damaged clips.

English

*** Thanks for your cooperation for the more quality. Please surely rate this document before closing.**

Cardiagn.Com